

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21431-00-00
Spot: CW2S2SE Sec/Twnshp/Rge: 16-29S-19W
990 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: RHODES Well Number: 1
County: KIOWA Total Vertical Depth: 5200 feet

Operator License No.: 6236
Op Name: M.T.M. PETROLEUM
Address: PO BOX 82
SPIVEY, KS 67142

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 688 WITH 200 SX CMT
Production: Size 4.5 feet: 5165 WITH 125 SX CMT
Liner: Size _____ feet: _____ 8/69.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/18/2001 1:00 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: SAND TO 5050' & 4 SX CMT. 1ST PLUG AT 1170' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 720' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/18/2001 3:00 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 5108-5111'. SANDED BACK TO 5050' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 1170' WITH 40 SX CMT. 2ND PLUG AT 720' WITH 40 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

INVOICED
DATE 6-27-01
NO. 2001062009
RECEIVED
KANSAS CORPORATION COMMISSION
JUN 27 2001
7 2001

Remarks: USED 604/04 POZMIX 6% GEL BY ALLIED. RECOVERED 2606' OF 4 1/2" CASING.

Plugged through: CSG

CONSERVATION DIVISION
6-27-2001

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

JUN 26 2001

Form CP-27