

1070108

TO: STATE CORPORATION COMMISSION API NUMBER 15-097-21,148-0000 SE SE SEC. 25, T 29 S, R 19 W

CONSERVATION DIVISION - PLUGGING SECTION 600 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 600 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME YOST C WELL # 1

TECHNICIAN'S PLUGGING REPORT 11/29 COUNTY KIOWA 165.82

OPERATOR LICENSE # 31925 WELL TOTAL DEPTH 5102 FEET

OPERATOR: QUALITY WELL SERVICE PRODUCTION CSG: SIZE 4 1/2" @ 4610' WITH 100 SX

NAME AND 249 BETH DR. SURFACE CASING: SIZE 8 5/8" @ 513' WITH 275 SX

ADDRESS STERLING, KS 67579

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 29 MONTH: 11 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4507-11; CIBP @ 4490', 4445-59. ANHYDRITE @ 1270'.

SAND BACK TO 4379' DUMP 4 SX CEMENT WITH BAILER. 1ST PLUG PERFORATE AT 1260'. PUMP 5 SX

GEL, 50 SX CEMENT, 5 SX GEL AT 1260'. NO CIRCULATION. PUMP AT 2 BPM AT 600' TO 350#.

HOLE STAYING FULL. SHOT PIPE AT 730'. PIPE FREE. 2ND PLUG PULL TO 530' PUMP 50 SX

CEMENT. GOOD CIRCULATION. 3RD PLUG PUMP 10 SX CEMENT AT 40'. GOOD CIRCULATION.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 29 MONTH: 11 YEAR: 1999

ACTUAL PLUGGING REPORT

SAND BACK TO 4379' DUMP 4 SX CEMENT WITH BAILER. 1ST PLUG PERFORATE AT 1260'. PUMP 5 SX

GEL, 50 SX CEMENT, 5 SX GEL AT 1260'. NO CIRCULATION. PUMP AT 2 BPM AT 600' TO 350#. HOLE

STAYING FULL. SHOT PIPE AT 730'. PIPE FREE. 2ND PLUG PULL TO 530' PUMP 50 SX CEMENT.

GOOD CIRCULATION. 3RD PLUG PUMP 10 SX CEMENT AT 40'. GOOD CIRCULATION.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 730' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 12/21/99

INV. NO. 061004

DEC 08 1999 SIGNED

12-8-1999

CONSERVATION DIVISION WICHITA, KS

(TECHNICIAN)

FORM CP-213-

(R)