

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

097-20,127-0002
API NUMBER 15- ABANDONED

C. SE NW 1/4 Sec. 4, T 29 S, R 16 W 14
_____ feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

_____ feet from W/E section line

Operator License # 5414

Lease Name Pyle Well # 2

Operator: J. MARK RICHARDSON
Name & Address 640 CENTURY PLAZA Bldg,
Wichita, KS 67202

County KIOWA

Well Total Depth 4715 feet \$153.24

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 302'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:00 AM Day: 20 Month: April Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Carl Shield

(company name) J. Mark Richardson (phone) _____

were: Plug off bottom w/ 50 sy cmt to 4015', then
recover pipe and pump down 8 5/8 using
50/50 lozmix, 2% gel - 3% CaCl, w/ following sequence:
2 sy hells, 10 sy gel, 50 sy cmt, 10 sy gel, 1 sy hells,
release plug and complete w/ 100 sy cmt.

Signed R. Barlutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:25 AM Day: 20 Month: April Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered.

Maximum pump pressure of 900 #
Shut in pressure of 300 #
Cementing by Allied.

Remarks: 4 1/2" set @ 4740 - Perfs @ 4710 - 4650 - loc. 670"

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1983

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

Signed R. Barlutton
(TECHNICIAN)

INVOICED

DATE 5-4-83

INV. NO. 4184-W

FORM CP-2/3
Rev. 9-82