

1 050997

1-28-88

0002 185

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 13-097-00122 - Bucket #E-24,506

SE SE SE, SEC. 12, T 29 S, R 20 WAE
330 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

330 feet from E section line

Operator: J. Mark Richardson
Name & Address: 640 Century Plaza Bldg.
Wichita, KS 67202

Lease Name Radar Well # 1

County Kiowa 166.56

Well Total Depth 5125 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 297

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor J. Mark Richardson License Number 5414

Address 640 Century Plaza Bldg., Wichita, KS 67202

Company to plug at: Hour: 9:30 a.m. Day: 28 Month: 1 Year: 19 88

Plugging proposal received from Carl Shields

(company name) J. Mark Richardson (phone) 316-862-5979

were: 4 1/2" at 5124' Perfs at 5030-34'

1st plug sand back to 4600' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 28 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

FEB 03 1988

Maximum pressure 600 psi and shut in 300 psi.

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2470' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED (circle / XXXXX) observe this plugging.

Signed Richard M. Jacey (TECHNICIAN)

DATE 2-4-88

INV. NO. 19729