

1 051809

5-10

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,233-0000  
C NE NW, SEC. 3, T 29 S, R 20 W  
4620 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414  
Operator: J. Mark Richardson  
Name & Address: 155 N. Market, Ste. 840  
Wichita, KS 67202

Lease Name Hayse D Well # 1  
County Kiowa 166.07  
Well Total Depth 5110 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 642

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Greensburg Well Service License Number 31201

Address 155 N. Market, Ste. 840, Wichita, KS 67202

Company to plug at: Hour: 10 a.m. Day: 10 Month: 5 Year: 1994

Plugging proposal received from Carl Schield

(company name) Greensburg Well Service (phone) 316-723-2204

Perfs: 4 1/2" at 5109' w/275 sx cement, PBD 4920', Perfs at 4389-92'

1st plug sand back to 4340' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 a.m. Day: 10 Month: 5 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3460' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION

MAY 12 1994

CONSERVATION DIVISION Wichita, Kansas

Signed Richard W. Lacey (TECHNICIAN)

INVOICED

DATE JUN 01 1994

INV. NO. 40514