

1 010224

MAR 16 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-21,232-0000

NE NE SE, SEC. 3, T 29 S, R 20 W/E

2310 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Lease Name Hayse C Well # 1

Operator: J. Mark Richardson
Name & Address: 640 Century Plaza Bldg.
Wichita, KS 67202

County Kiowa 165.75

Well Total Depth 5100 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 613

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Gabbert-Jones, Inc. License Number 5842

Address 333 East English #215, Wichita, KS 67202

Company to plug at: Hour: 3 a.m. Day: 16 Month: 3 Year: 19 87

Plugging proposal received from Carl Shields

(company name) J. Mark Richardson (phone) 316-262-3192

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2371'
Anhydrite 1200'

1st plug at 1200' with 50 sx cement, 2nd plug at 750' with 50 sx cement,

3rd plug at 400' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement.

Plugging Proposal Received by Jack Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5 a.m. Day: 16 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1200' with 50 sx cement,

2nd plug at 750' with 50 sx cement,

3rd plug at 400' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

3-18-1987

INVOICED (did not) observe this plugging.

Signed Jack Luthi (TECHNICIAN)

STATE CORPORATION COMMISSION

MAR 18 1987

CONSERVATION DIVISION
Wichita Kansas

DATE 3-20-87

INV. NO. 16365 3-16 MAY 14 1987

JUL 08 1987

FORM CP-2/3
Rev. 01-84

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 3 - 02 - 87 month day year

API Number 15- 097-21,232-0000

OPERATOR: License # 5414 Name J. Mark Richardson Address 640 Century Plaza Bldg. City/State/Zip Wichita, Kansas 67202 Contact Person J. Mark Richardson Phone (316) 262-3192

NE NE SE Sec. 3 Twp. 29 S, Rg. 20 2310 330 Ft. from South Line of Section Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet County Kiowa

CONTRACTOR: License # Gabbert-Jones, Inc. City/State Wichita, Kansas

Lease Name Hays, C. Well # 1 Ground surface elevation 2371 feet MSL

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary Gas Inj X Pool Ext Air Rotary OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Depth to bottom of fresh water 200 Depth to bottom of usable water 290

Surface pipe by Alternate: 1 X 2 Surface pipe planned to be set 600

Conductor pipe required Projected Total Depth 5100 feet

Formation Mississippi

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 2-13-87 Signature of Operator or Agent J. Mark Richardson Title Operator

For KCC Use: Conductor Pipe Required 300 feet; Minimum Surface Pipe Required 300 feet per Alt. This Authorization Expires 8-24-87 Approved By 2-21-87

SPUD - 3-4-86

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, cement quantity, and mousehole details. Includes rows for 1st through 5th plugs and a rathole.

CARL SHIELDS - W/

Vertical log entries: PUSHER TD 5100 FORMATION M.S.S. SURFACE PIPE 8 1/2 @ 6.13 ANHYDRITE ELEVATION STARTING TIME & DATE 3:00 3-16 COMPLETION TIME & DATE 5:00 3-16-87 1st PLUG @ 1200 FT. W/ 50 SX 2nd PLUG @ 750 FT. W/ 50 SX 3rd PLUG @ 400 FT. W/ 50 SX 4th PLUG @ 0-40 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 10 SX MOUSE HOLE CIRCULATED W/ NA SX WATER WELL PLUGGED W/ 20 CEMENT COMPANY Allied TECHNICIAN Dr. Kelly 60/40 690

STATE CORPORATION COMMISSION MAR 12 1987 CONSERVATION DIVISION Wichita, Kansas