

To: 1090787 3-18
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-097-20,299-0000
C NW, SEC. 6, T 29 S, R 20 W/EX
3960 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5988
Operator: Halliburton Oil Producing Company
Name & Address: 525 Central Park Dr., Central Park I Ste. 210
Oklahoma City, OK 73105
1001 NW 63rd St S. 250
OKLA. City, OK 73116

Lease Name Rudd Well # 1-6
County Kiowa 168.90
Well Total Depth 5197 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 530

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 2:30 p.m. Day: 18 Month: 3 Year: 19 97
Plugging proposal received from Manny Boatwright

(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

work: 4 1/2" at 5197' w/125 sx cement, Perfs at 5050-58, 5072-76, 5086-92, 5108-16'
1st plug sand back to 5000' and dump 4 sx cement on top of sand through bailer,
2nd plug at 1360' with 50 sx cement,
3rd plug at 560' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 p.m. Day: 18 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 5000' and dumped 4 sx cement on top of sand through bailer,

2nd plug pulled to 1361' and spotted 10 sx gel and 50 sx cement,
3rd plug pulled to 563' and spotted 50 sx cement,
4th plug pulled to 40' and circulated 10 sx cement to surface.

Stayed full.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 4 1/2" casing.
(If additional description is necessary, use BACX of this form.)

Observe this plugging.

Signed [Signature] (TECHNICIAN)

INVOICED

DATE 3-19-97

INV. NO. 47776

3-18

RECEIVED
KANSAS CORP. COMM
MAR 20 11:40