

1 060861

No: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,779-0000

S/2 SE, SEC. 8, T 29 S, R 20 (W)

660 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5254

Lease Name Neier Well # 1

Operator: Midco Exploration

County Kiowa 170.43

Name & Address 411 Farmers & Bankers Building

Well Total Depth 5244 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 607

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:30 am Day: 7 Month: July Year: 19 86

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 5223' PBD 5240' Perfs at 5092-96'

1st plug sand back to 5040' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 50 sx cement, 10 sx gel, 1 sack hulls, and 120 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:15 am Day: 7 Month: July Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 5040' and dumped 5 sx cement on top of

sand through bailer, 2nd plug squeezed well with 2 sx hulls, 50 sx cement, 10 sx gel, 1 sack hulls and 120 sx cement.

Maximum pressure 325psi and shut in 50 psi

Remarks: Recovered 4027' 4 1/2" casing. Used 60/40 Pozmix by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED JUL 14 1986

observe this plugging STATE CORPORATION COMMISSION

Signed Paul A. Luthi (TECHNICIAN)

DATE

JUL 11 1986

INV. NO. 14360

CONSERVATION DIVISION Wichita, Kansas