

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21306-00-00
Spot: NWSW Sec/Twnshp/Rge: 9-29S-20W
1980 feet from S Section Line, 4629 feet from E Section Line
Lease/Unit Name: NEIER B Well Number: 1
County: KIOWA Total Vertical Depth: 5148 feet

Operator License No.: 5414 Conductor Pipe: Size _____ feet:
Operator Name: RICHARDSON, J. MARK/RICHARD Surface Casing: Size 8.625 feet: 478
Address: 2843 KEYWEST CT. Production: Size 4.5 feet: 5148 *167.31*
WICHITA, KS 67204 Liner: Size _____ feet:
9/14

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/14/2000 9:30:00 AM

Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.

Proposal Rcvd. from: CARL SCHIELD Company: RICHARDSON, J. MARK/RICHARD Phone: (316) 546-3410

Proposed Plugging Method: SAND TO 5000' WITH 4 SX CMT WITH BAILER. PUMP 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8 WIPER PLUG - 150 SX CEMENT

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/14/2000 10:30 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PERFS AT 5063-67. SAND TO 5000' WITH 4 SX CMT ON TOP. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8 WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 300#.

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 2000

CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3750' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

INVOICED

DATE 9/22/00

SEP 15 2000

Form CSG

WV. NO. 2001060725

MP

L