

1 051808

5-10

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,941-0000

C SE NE, SEC. 12, T 29 S, R 20
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414
Operator: J. Mark Richardson
Name
Address 155 N. Market, Ste. 840
Wichita, KS 67202

Lease Name Rader Well # 2
County Kiowa 167.05
Well Total Depth 5140 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 651

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Greensburg Well Service License Number 31201

Address 155 N. Market, Ste. 840, Wichita, KS 67202

Company to plug at: Hour: 1:30 p.m. Day: 10 Month: 5 Year: 1994

Plugging proposal received from Carl Schield

(company name) Greensburg Well Service (phone) 316-723-2204

Perfs: 4 1/2" at 5139', Perfs at 5048-51'

1st plug sand back to 5000' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 10 Month: 5 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back to 5000' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

RECEIVED STATE CORPORATION COMMISSION

MAY 12 1994

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2660' of 4 1/2" casing (if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

INVOICED

DATE JUN 01 1994
INV. NO. 40513
5-10