

To: 1 090212
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-4

API NUMBER 15- 097-21,269--0000
C NW NE, SEC. 17, T. 29 S, R 20 W/R
4620 feet from S section line
1980 feet from E section line

STR

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Lease Name Miller Well # 1

Operator: J. Mark Richardson

County Kiowa 170.30

Name & Address 155 N. Market, Suite 840

Well Total Depth 5240 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 612

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Greensburg Well Service License Number _____

Address 303 E. Kansas, Greensburg, KS 67054

Company to plug at: Hour: 10 a.m. Day: 4 Month: 9 Year: 19 92

Plugging proposal received from Carl Schield

(company name) Greensburg Well Service (phone) 316-723-2204

were: 4 1/2" at 5240' w/275 sx cement, PBTD 5180', Perfs at 5132-35, 5127-29, 5114-16'

1st plug sand back to 5060' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 4 Month: 9 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 5060' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 150 sx cement. Filled water well with cement.

Maximum pressure 500 psi and shut in 150 psi.

RECEIVED
STATE CORPORATION COMMISSION
9-10-1992

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3525' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

1 (did / ~~not~~) observe this plugging.

INVOICED

DATE 10-7-92

INV. NO. 36358

Signed [Signature]
(TECHNICIAN)

SEP 10 1992
CONSERVATION DIVISION
Wichita, Kansas