

1 050402

*RV*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,082-000

C NE NE     , SEC. 18; T 29 S, R 20  W  E

4620 feet from  S section line

660 feet from  E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9869

Lease Name McDermet Well # 1

Operator: Chapman Energy Oklahoma, Inc.

County Kiowa

Name & Address 120 South Market, Suite 320

Well Total Depth 5275 <sup>171.44</sup> feet

Wichita, KS 67202

Conductor Pipe: Size      feet

Surface Casing: Size 8 5/8 feet 600

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D&A X

Other well as hereinafter indicated     

Plugging Contractor Wheatstate Oilfield Services License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 6:00 pm Day: 12 Month: December Year: 19 84

Plugging proposal received from Dennis Petz

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1350' with 50 sx cement

2nd plug at 630' with 40 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Leem  
(TECHNICIAN)

Plugging Operations attended by Agent?: All      Part      None X

Operations Completed: Hour: 8:00 pm Day: 12 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1350' with 50 sx cement, 2nd plug at 630' with 40 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate

mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(if additional description is necessary, use BACK of this form.)

I ~~did~~ / did not observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS  
DEC 18 1984  
12-18-1984

Signed Richard W. Leem  
(TECHNICIAN)

INVOICED  
DATE 12-26-84  
INV. NO. 6156