

1100371

TO: STATE CORPORATION COMMISSION

API NUMBER 15-097-21,455-0000  
C W/2 NE SEC. 22, T 29 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 3960 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SCOTT WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA 168.35

OPERATOR LICENSE # 8061 7/7

WELL TOTAL DEPTH 5180 FEET

OPERATOR: OIL PRODUCERS INC. OF KS PRODUCTION CSG: SIZE        " FEET

NAME AND PO BOX 8647 SURFACE CASING: SIZE 8 5/8" @ 681' WITH        SX

ADDRESS WICHITA, KS 67208

ABANDONED OIL WELL        GAS WELL        INPUT WELL        SWD WELL        D/A X

OTHER WELL AS HEREINAFTER INDICATED       

PLUGGING CONTRACTOR MALLARD JV INC LICENSE NUMBER 4958

ADDRESS PO BOX 905, MCPHERSON, KS 67460

COMPANY TO PLUG AT: HOUR: 4:45 AM DAY: 07 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM       

(COMPANY NAME) MALLARD JV INC (PHONE) 316-241-4640

RECEIVED  
STATE CORPORATION COMMISSION

WERE:       

JUL 14 2000  
7-14-2000  
CONSERVATION DIVISION  
Wichita, Kansas

1ST PLUG AT 1350' WITH 80 SX CEMENT. 2ND PLUG AT 720' WITH 50 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

       PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL        PART        NONE X

OPERATIONS COMPLETED: HOUR: 6:00 AM DAY: 07 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1350' WITH 80 SX CEMENT. 2ND PLUG AT 720' WITH 50 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

DATE 7/18/00 SIGNED Gary Winters

(TECHNICIAN)

FORM CP-2/3

WV. NO. 1060076

✓

*[Handwritten signature]*