

To: 1031389  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-097-2190-00-00  
NE NE SW, SEC. 12, T 29 S, R 20 W/E

TECHNICIAN'S PLUGGING REPORT **2-22**  
Operator License # 5414  
Operator: J. Mark Richardson  
Name & Address: 155 N. Market, Ste. 840  
Wichita, KS 67202

2310 feet from S section line  
2970 feet from E section line  
Richardson-Alberts  
Lease Name Well # 1  
County Kiowa  
Well Total Depth 5827 189.38 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 13 3/8 feet 353

Abandoned Oil Well Gas Well Input Well X SWD Well D&A  
Other well as hereinafter indicated

Plugging Contractor Greensburg Well Service License Number  
Address 303 E. Kansas, Greensburg, KS 67054

Company to plug at: Hour: 9:30 a.m. Day: 22 Month: 2 Year: 19 96

Plugging proposal received from Carl Schield  
(company name) Greensburg Well Service (phone) 316-723-2204

logs: 4 1/2" at 5799' w/300 sx cement, PBSD 5770', Perfs at 5243-45, 5062-66, 5061-65, 4745-51,  
4754-60, 4483-87, BP @ 5185'

1st plug at 600' with 50 sx cement,  
2nd plug at 360' with 50 sx cement,  
3rd plug at 40' with 20 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:30 a.m. Day: 22 Month: 2 Year: 19 96

ACTUAL PLUGGING REPORT  
1st plug at 600' with 3 sx gel and 50 sx cement,  
2nd plug at 360' with 50 sx cement,  
3rd plug at 60-0' with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 600' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I should observe this plugging.

DATE 3-4-90  
INV. NO. 44922  
2-22

Signed Steve Durrant  
(TECHNICIAN)

RECEIVED  
KANSAS DOR COM  
1996 FEB 26 9:41