

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1966
4-26-66
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Ralstin Well No. # 1

Location C NW NE Sec. 2 Twp. 29 Rge. 20 (E) (W) W

County Kiowa Total Depth 5070'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Rains & Williamson Oil Company

Address: 1425 Wichita Plaza Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 12:15 PM Day 25th Month April Year 1966

The Above well was plugged as follows:

292' of 8 5/8" surface pipe, cement circulated with 275 sacks. Hole
was filled with drilling mud to 275', 1st cementing plug, bridged solid
with dry cement and 1/4 sack of hulls on fluid at 275', and cemented with
25 sacks. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged solid with dry cement and hulls on fluid at 40', and cemented
with 10 sacks to the base of the cellar. Rat hole bridged and cemented
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 4/26/66
INITIALS 3116-W

Signed: Aubie Elving
Well Plugging Supervisor