

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed June 6, 1967.

RECEIVED
STATE CORPORATION COMMISSION
JUL 3 1967
7-3-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Graham-Michaelis Drilling, Inc.
Complete Address 211 N. Broadway, Wichita, Kansas 67202
Lease Name Rudd Well No. # 1-14
Location C NW SE Sec. 14 Twp. 29 Rge. 20 (E) W (W) W
County Kiowa Total Depth 5216'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Graham-Michaelis Drilling, Inc.
Address 211 N. Broadway, Wichita, Kansas License No.
Operation Completed: Hour 10:00 A.M. Day 29th Month June Year 1967

The above well was plugged as follows:

566' of 8 5/8" surface pipe, cement circulated with 325 sacks. Hole
was filled with drilling mud to 400', 1st cementing plug, bridged with
1/2 sack of hulls on fluid at 400', and cemented with 25 sacks. Hole was
filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack
of hulls on fluid at 40', and cemented with 10 sacks to the base of the
cellar. Rat hole bridged and cemented with 2 sacks.

This cementing was done by Sun Cementing Company

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/3/67
INV. NO. 5510-W

Signed: Archie Elving
Well Plugging Supervisor