

15-097-00136-0000

Form CP-3  
Rev. 6-26-62

*J*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
CORPORATION COMM  
FEB 14 1967  
2-14-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued February 3, 1967.

Operator's Full Name Alpine Oil & Royalty Company, Inc.

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name Rice Well No. # 1

Location NE NE NE Sec. 19 Twp. 28 Rge. 18 (E) (W) W

County Kiowa Total Depth 4894'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 9:15AM Day 13th Month Feb. Year 1967

The Above well was plugged as follows:

300' of 8 5/8" surface pipe, cemented with 200 sacks. 4894' of 5 1/2" long  
string, cemented with 200 sacks. Plug back T.D. 4320'. Top perforation  
4258'. Bottom of the hole was sanded to 4250', and cemented with 5 sacks,  
through the dump bailer. 3700' of 5 1/2" long string was recovered from the  
hole. Bridge plug was pushed in fluid to 305', bridge plug and rock bridge  
from 305' to 295'. 3 sacks of cement was mixed in a barrel, and put on plug  
at 295', through the dump bailer, and let set over-night. Next day hole was  
bailed dry, and filled with 4 1/4 yards of ready-mix cement from 285' to the  
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 2/14/67

INV. NO. 4756-u