

*R*

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

DEC 14 1964  
12-14-64  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Apache Corporation 15-097-00233-0000

Complete Address: 823 South Detroit, Tulsa, Oklahoma

Lease Name Nolan Well No. # 1

Location C NE SW Sec. 28 Twp. 28 Rge. 17 (E) (W) W

County Kiowa Total Depth 4889

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 9:30PM Day 11th Month Dec. Year 1964

The Above well was plugged as follows:

251' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid  
was up in the hole. 1st cementing plug and 1/2 sack of hulls was pushed  
in fluid to 240', and cemented with 25 sacks, through the drill pipe.  
Hole was filled with drilling mud to 40', bridged solid with hulls, and  
cemented with 10 sacks to the base of the cellar. Rat hole bridged and  
cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 12-14-64  
INV. NO. 335-W