

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-097-00187-00-01

FILE NO. 8-40

LOCATION C-SW-NW

SEC. 26 TWP. 28 RGE. 17-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Cross

Operator Bishop Oil Company Address #901 Brown Bldg - Wichita

Field _____ County Kiowa

Total Depth 4916 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 1150 ft - Circulated with Cement
5 1/2" casing set at 4916 ft cement & Well Packed No Oil
Plugged back from bottom to 4812 ft with Four Wells Plugs
& Cement - Filled with Mud from 4812 ft to 4760 ft - Bridge
& 5 sacks Cement at 4750 ft - Shot off & recovered 3700 ft of 5 1/2"
Cas - 9 - Mud to 1100 ft - Plug & 15 sacks of Cement -
Mud to 25 ft - Plug & 10 sacks Cement

G. W. Stough
District Conservation Agent

Date: 2-21-48

PLUGGING
FILE SEC 26 T 28 R 17W
BOOK PAGE 8 LINE 10

2-24-48