

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 9 1964

CONSERVATION DIVISION  
Wichita, Kansas

11-9-64

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply Inc.

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Rice Well No. # 1

Location C SW SE Sec. 18 Twp. 28 Rge. 18 (E) (W) W

County Kiowa Total Depth 4919

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 12:00PM Day 5th Month Nov. Year 1964

The Above well was plugged as follows:

361' of 8 5/8" surface pipe, cemented with 225 sacks. 4919' of 4 1/2" long  
string, cemented with 200 sacks. Top perforation 4284'. Push plug to  
4275', and 20' of sand, cemented with 3 sacks. Fluid level in the hole  
was at 65'. Bridge plug was pushed in fluid to 275', and 10' of rock  
bridge. 2 sacks of cement was mixed in barrel, and put on plug at 265'  
through the dump bailer, and let set over-night. Next morning hole was  
bailed dry, and 23 sacks of cement was added to plug. Hole was filled  
with mud to 40', and 10' of rock bridge, and cemented with 10 sacks to  
the base of the cellar. 2278' of 4 1/2" long string was recovered from the hole.  
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elwing  
Well Plugging Supervisor

DATE 11/9/64

INV. NO. 123-11