

KANSAS

FORM CP-3  
Rev. 5-5-81

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
9-17-81  
SEP 17 1981

API Number 15-097-20-791-000 CONSERVATION DIVISION  
Wichita, Kansas

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name Kan - Exp. Inc.  
S. M. Oil Co.

Complete Address 4921 W. 83rd St. Prairie Village, Mo.

Lease Name Bergner Well No. 1

Location E-NE NW Sec. 20 Twp. 28S Rge. 16W (East) (West)

County Kiowa Total Depth 4835

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Mustang Drilling Co.

Address Box 1609 Great Bend Kans License No. \_\_\_\_\_

Operation Completed: Hour: 8:30 PM Day: 13 Month: September Year: 19 81

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

There is 413' of 8 3/8" surface casing cement circulated with 300 lbs of 3% calcium chloride & 2% Jell. The hole was kept full of heavy mud circulated at 360'. 1st plug, rubber plug pushed to 360' then put 40 lbs of cement on top of rubber plug. 2nd plug 1 lb of hulls & 10 lbs of cement put on solid bridge at 40' to 0'. They put 5 lbs of cement in rat hole, there was no mouse hole. Plugging accomplished by Sun cementing of Great Bend Kans.

I hereby certify that the above well was plugged as herein stated.

Signed: Paul Luthie  
Conservation Division Agent

NOTICED  
DATE 10-29-81  
INV. NO. 8139-W