

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 26 1966

4-26-66

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Gale Metz of Rains & Williamson Oil has this
 date requested permission to plug the following described well:

Mr. Metz guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name: Ralstin Well No. # 1

Location: C NW NE Sec. 2 Twp. 29 Rge. 20 (E)(W) W

County Kiowa Total Depth 5070' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Metz was instructed to plug the well as follows:

292' of 8 5/8" surface pipe, cement circulated with 275 sacks.

Fill hole with drilling mud to 275', 1st cementing plug, bridge with

1/4 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud

to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with

10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent