



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

30-December 1981

VERBAL PERMIT FORM (To be filed by Plugging Agent)

15-097-20842-0000

Dear Sir:

Mr. Lyle Cason of Union Drilling Co. Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Midea Exploration Inc.

Complete Address: 411 Farmers & Bankers Bldg. Wichita, Kansas 67202

Lease Name: Wheeler Well No. 1

Location: C-NW-NE Sec. 35 Twp. 28 Rge. 17 1/2 (E) (W)

County: Kiowa Total Depth: 4973'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Cason was instructed to plug the well as follows:

There is 370' of 8 1/2" surface casing cement circulated. 1st plug at 1200' with 35 sbp of cement. 2nd plug pushed rubber plug to 350' and pumped 35 sbp of cement on top of it. 3rd plug at 40' to 0' with 10 sbp of cement on solid bridge. Then pumped 10 sbp of cement in rat hole. The farmer wants water, will so they were advised about recording it with K. C. C. The plugging was accomplished by Sun Cementing. RECEIVED
Very truly yours,
STATE CORPORATION COMMISSION

JAN - 5 1982

CONSERVATION DIVISION
Wichita Kansas

Paul Little
Conservation Division Agent

1-5-82