

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 3 1967

CONSERVATION DIVISION
Wichita, Kansas
7-3-67

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed June 6, 1967.

Dear Sir:

Mr. Tom Curtis of Graham-Michaelis Drlg has this
date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Drilling, Inc.

Complete Address: 211 N. Broadway, Wichita, Knasas 67202

Lease Name: Rudd Well No. #1-14

Location: C NW SE Sec. 14 Twp. 29 Rge. 20 (E)(W) W

County Kiowa Total Depth 5216' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Curtis was instructed to plug the well as follows:

566' of 8 5/8" surface pipe, cement circulated with 325 sacks. Fill
hole with drilling mud to 400', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent