

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-097-30171-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1968

CONSERVATION DIVISION
Wichita, Kansas

11-23-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bill Draper of Gabbert-Jones, Inc. has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Alpine Oil & Royalty Company, Inc.

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name: Cecil Vieux Well No. # 1

Location: C NE SW Sec. 19 Twp. 28 Rge. 18 (E) (W) W

County Kiowa Total Depth 5062' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

321' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of the cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent