

15-017-20634-00-01

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Kiowa SEC. 25 TWP. 28S RGE. 16 ~~XX~~/W
 Location as in quarters or footage from lines:

Lease Owner Plano Petroleum
 Lease Name Greiner Well No. 1
 Office Address Box 247 Plano, TX
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry
 Date Well Completed August, 1983
 Application for plugging filed 11-15-83
 Plugging commenced 12-7-83
 Plugging completed 12-27-83
 Reason for abandonment of well or producing formation Not economical to produce

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Richard Lacey
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4727'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record


Formation	Content	From	To	Size	Put in	Pulled Out
		0	398'	8 5/8		0
		398		4 1/2		1450'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set. PB TD 4723'. Sand fillup to 4630', dumped 4 sx.
of common cement to fillup of 4630'. Shot casing off at 3900 ft., not loose, shot
casing 3100 ft., not loose. Dialog cut off at 1450 ft. POOH.
Final plugging: 3 sx. hulls, 10 sx. gel, 50 sx. cement, 10 sx. gel, 1 sx. hulls,
8 5/8" wiper plug, 100 sx. cement, 60/40 poz mix, 2% gel--3% C.C. Max. pressure,
700#, ISIP 450#, job complete 2:30 P.M.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pratt Well Service, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.
Judy Berry (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.



(Signature) Judy Berry
Box 847 Pratt, Ks.
 (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of January, 19 84

Charlene M. Dudrey
 Notary Public

My Commission expires: 9/10/86

RECEIVED
 STATE CORPORATION COMMISSION

1-10-1984 JAN 10 1984