

15-097-00045-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas


WELL PLUGGING RECORD

Kiowa County, Sec. 16 Twp. 28 Rge. 16 (E) W (W)

Location as "NE/CNWSW" or footage from lines NW NW SE
Lease Owner American Petrofina Co. of Texas
Lease Name Kinney "A" Well No. 1
Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed December 23, 1955 12-23-55
Application for plugging filed March 28, 1962 3-28-62
Application for plugging approved March 29, 1962 3-29-62
Plugging commenced 4-7-62 19
Plugging completed 4-11-62 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4830' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	365'	None
				5-1/2"	4800'	3915'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4770', ran 50 gal. of sand and dumped 5 sacks of cement with dump bailer. Pulled 5 1/2" casing. Checked fluid to 310', set rock bridge to 300' and dumped 20 sacks of cement. Mudded to 200', let set over night, mudded to 40' set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.



(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

4-16-1962

STATE OF Kansas COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of April, 19 62

May 20, 1964

Milton J. Volin
Notary Public.

My commission expires _____



BEN F. BRACK OIL COMPANY, INC.
 309-10 BROWN BUILDING
 WICHITA 2, KANSAS

15-097-00045-0660

KINNEY #1

NW NW SE

Sec. 16-288-16W
 Kiowa County, Kansas
 Commenced: 12-5-55
 Completed: 12-23-55

TOTAL DEPTH: 4830'

WELL LOG

Surface Soil & Shale	0 -	70'
Sand & Gravel		160
Shale		365
Red Bed & Gypsum Shells		430
White Sand & Gypsum Shells		440
White Sand & Iron Pyrite		455
Shale & Shells		1080
Anhydrite		1110
Shale & Shells		1280
Red Bed, Sand & Shale		1810
Shale, Shells, & Sand		2025
Shale & Lime		2225
Lime		2365
Lime & Shale		2450
Lime		2674
Lime & Shale		2770
Lime		2830
Lime & Shale		3005
Lime		3130
Lime & Shale		3390
Lime		3465
Lime & Shale		3640
Lime		3750
Shale & Chalky Lime		3852
Lime & Shale		3881
Lime		4043
Lime, Shale & Sand		4070
Lime & Shale		4144
Lime		4700
Lime & Shale		4720
Lime & Chert		4754
Lime		4783
Shale w/Lime Streaks		4814
Lime		4830 T.D.

RECORDED
 MAR 23 1962
 COMMISSIONER DIVISION
 WICHITA, KANSAS

The above depths denote bottom of formations.

CASING

Perf 4729-39 40 holes 8 5/8" 365' - 250' 5/8"
 5 1/2" 4800' - 125' 5/8"

To the best of my knowledge, the above is a true and correct statement of the depths and formations and where found.

BEN F. BRACK OIL COMPANY, INC.

E Bernard W. Grant

WITNESSED

Estelita Crist

August 27, 1955