

15-097-10017-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kiowa County. Sec. 16 Twp. 28s Rge. 16 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SW NE

Lease Owner American Petrofina Company of Texas

Lease Name Kinney "B" Well No. 1

Office Address Box 209 - Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed October 9 19 57

Application for plugging filed November 20 19 58

Application for plugging approved November 21 19 58

Plugging commenced December 19 19 58

Plugging completed January 8 19 59

Reason for abandonment of well or producing formation Insufficient Production

If a producing well is abandoned, date of last production May 1 19 58

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W.L. Lackamp, Stafford, Kansas.

Producing formation Cherokee Sand Depth to top 1706 Bottom 4725 Total Depth of Well 4825 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	363'	0' <del>358'</del>
				5 1/2"	4812'	3607.40'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped 50 sacks of cement to 4400'

Mudded to 300'

Set bridge and run 20 sacks of cement at 300'

Mudded to 35'

Run 10 sacks of cement to cap.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 13 1959

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C. E. Shull Casing Pulling Company

Address Box 558 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
LEVI B. SHERMAN (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Levi B. Sherman  
Box 209 Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January, 19 59

Carroll J. Bennett  
Notary Public.

My commission expires 10-2-60

PLUGGING  
FILE SEC. 16 T 28 R 16W  
BOOK PAGE 146 LINE 44

COPY

15-097-10047-0000

ROTARY DRILLING LOG

OPERATOR: El Dorado Refining Co.  
SE SW NE, Sec. 16-28S-16W  
Kiowa County, Kansas  
KINNEY #1 "B"

CONTRACTOR: Prim Drilling Co.  
COMM: 9-24-57  
COMPL: 10-9-57

Remarks: Set 8 5/8" Surf. csg  
at 363'. Cx. w/250 sx.  
common cx. 2% C. C.

FORMATIONS

Shale	70'
Sand	195'
Shale & shells	363'
Red Bed & Shale	460'
Red Bed, Shale & Shells	1070'
Anhydrite	1112'
Shale, Red Bed & Shells	1600'
Shale & Shells	2175'
Shale & Lime	2250'
Lime	2550'
Lime & Shale	2655'
Lime	2730'
Lime & Shale	2840'
Lime	2930'
Lime & Shale	3780'
Lime	3985'
Lime & Shale	4140'
Lime	4638'
Shale & Lime	4695'
Lime	4735'
Mississippi	4825'
Rotary Total Depth	4825'

SAMPLE TOPS

Heeb.	4023
Tor.	4045
Doug.	4066
Br. Lm.	4182
Lans.	4200
BKC	4560
Cher. Shale	4688
Cher. Sand	4706
Reworked Miss.	4726
Kind.	4795
RTD	4825

Set 5 1/2" casing at 4812', cx. w/125 sacks  
common cx.

We certify the above log is true and correct  
to the best of our knowledge, and belief.

PRIME DRILLING COMPANY

S/ R.R. McNicol

RECEIVED  
STATE COMMISSION  
NOV 21 1958  
OIL & NATURAL GAS DIVISION  
Topeka, Kansas

PLUGGING	
FILE SEC	16 T 28 R 16W
BOOK PAGE	146 LINE 44

15-097-10017-0000

Brief Plugging Record on  
American Petrofina Co. of Texas's  
Kinney "B" Well #1, in  
Kiowa County, Kansas

---

Total depth 4825'

5½" casing set at 4812'

Cemented with 125 sacks

8 5/8" casing set at 363'

Cemented with 250 sacks

Pumped 50 sacks of cement to 4400'

Mudded to 300'

Set bridge and run 20 sacks of cement at 300'

Mudded to 35'


Run 10 sacks of cement to cap

Work started December 19, 1958

Work completed January 8, 1959

C. E. Shull Casing Pulling Company  
Box 558  
Great Bend, Kansas

License No. 8



RECEIVED  
STATE CORPORATION COMMISSION

JAN 13 1959

CONSERVATION DIVISION  
Wichita, Kansas