

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-897-20259-0000

LEASE NAME Schaul

WELL NUMBER #1

SPOT LOCATION 1320 ENL-33@EWL

SEC. 15 TWP. 28 RGE. 16 (X) or (W)

COUNTY Kiowa

Date Well Completed 12-13-74

Plugging Commenced 2-3-84

Plugging Completed 2-10-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texas Oil and Gas Corp.

ADDRESS Suite 300 - 200 W. Douglas- Wichita, KS 67202

PHONE # () OPERATORS LICENSE NO. X 5171

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Lacey and Luthi

Is ACO-1 filed? If not, is well log attached?

Producing formation Depth to top bottom T.D. 4724

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	450	None
				4 1/2	4730	2650

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plugged back at 4702.
Sun Cementing pumped in 35 sacks cement. Stopped plug at 4100. Sun pumped in 2 sacks hulls - 10 sacks jell - 50 sacks cement - 10 sacks jell - 15 sacks hulls - Dropped plug. 125 sacks cement. 60-40 POZ 2% jell - 3% C.C.

Zimmerman on location. Luthi OK

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105
Address P O Box 187 - Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Barber, ss.

Elmo Morgenstern (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Elmo Morgenstern*
(Address)

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1984
SUBSCRIBED AND SWORN TO before me this 14 day of February, 1984
2-15-1984 Pamela Ricks
Notary Public

My Commission expires: 10-11-87

15-097-20259-0000

DRILLERS' LOG

TEXAS OIL & GAS CORP.
No. 1 Schaul
1320' FNB & 330' FWL NW/4,
Sec. 15-28S-16W
Kiowa County, Kansas

Elev: 2152 K.B.

Commenced: 12-2-74
Completed: 12-13-74

Surface: 443' of 8-5/8"
cemented w/130 sx common
cmt, 4% Gel, 2% cc. 12-3-74

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 450
Red Bed & Shale	450 - 1446
Red Bed & Lime Streaks	1446 - 1785
Shale & Lime	1785 - 2570
Lime & Shale	2570 - 3280
Lime	3280 - 3795
Lime & Shale	3795 - 3967
Lime	3967 - 4610
Lime & Shale	4610 - 4645
Lime	4645 - 4699
Lime & Chert	4699 - 4731 T.D.

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 17th day of December, 1974.

My Commission Expires:
August 25, 1976

Ella Priess
Ella Priess, Notary Public

RECEIVED
STATE CORPORATION COMMISSION

NOV 2 1983

CONSERVATION DIVISION
Wichita, Kansas

Ella Priess
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Com. Expires Aug. 25, 1976