

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Kiowa County, Sec. 15 Twp. 28S Rge. ~~XX~~ 16 (W)

Location as "NE/CNW/SW" or footage from lines C NE NW SW

Lease Owner Gulf Oil Corporation

Lease Name J. Phillips Well No. 1

Office Address Box 661, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 12-18 1956

Application for plugging filed 10-11 1957

Application for plugging approved 10-15 1957

Plugging commenced 10-17 1957

Plugging completed 10-24 1957

Reason for abandonment of well or producing formation Well was producing below its economic limit.

If a producing well is abandoned, date of last production 9-16 1957

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Mississippi chert Depth to top 4720' Bottom 4761' Total Depth of Well 4825' Feet

Show depth and thickness of all water, oil and gas formations. PBTD 4769 Feet

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	1116'	0
				4-1/2"	4803'	3847'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with sand to 4700'. Spotted 4 sacks cement at 4700'. Filled with mud from 4700' to 300'. Set rock bridge and spotted 25 sacks cement at 300'. Filled with mud to 25'. Spotted rock bridge and 10 sacks cement which filled hole into cellar.

NOTE: W. C. Bunch - Special Petty Cash, Check No. 1780, dated 10-25-57, in the amount of \$ 47.69 is attached.

RECEIVED  
OCT 29 1957  
10-29-1957  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service

Address 102 West Eighteenth Street, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Lloyd L. Gray (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lloyd L. Gray

Box 2233, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 25th day of October, 1957

My commission expires 6-3-61

Notary Public.

JRM:PF

PLUGGING  
FILE SEC 15 T 28 R 16 W  
BOOK PAGE 53 LINE 14

15-697-60134-0000

WELL LOG

COMPANY: Gulf Oil Corporation  
 FARM: John Phillips No. 1  
 TOTAL DEPTH: 4825'  
 CORR: 11-22-56. COMP: 12-13-56.

Section 15-288-16W  
 Location - NE NW SW  
 County - Kiowa

CASING

10-3/4" - 446'  
 4-1/2" - 4824'

ELEVATION

D.F. -  
 Cr. -

DRILLER'S LOG

Sand & Red Bed	0	467
Red Bed	467	930
Red Bed & Shale	930	1655
Shale & Shells	1655	2274
Shale & Lime	2274	2409
Shale	2409	2499
Shale & Lime	2499	3300
Shale	3300	3394
Sandy Lime & Shale	3394	3504
Lime & Shale	3504	3881
Lime	3881	4102
Shale & Lime	4102	4215
Lime	4215	4303
Cherty Lime	4303	4350
Lime	4350	4697
Core No. 1	4697	4718
Core No. 2	4718	4727
Core No. 3	4727	4749
Chert	4749	4750
Core No. 4	4750	4778
Chert & Lime	4778	4825
Total Depth		4825

RECEIVED  
 STATE CORPORATION  
 OCT 12 1957  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

PLUGGING  
 FILE SEC. 15 T. 28 R. 16 W  
 BOOK PAGE 53 LINE 14