

15-097-20642-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County. Sec. 1 Twp. 285 Rge. 16-WE/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
2310 FSL 2310 FEL

Lease Owner Texas Oil and Gas
Lease Name Binford Well No. 1
Office Address 200 W. Douglas, Suite 300, Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) 67202
Gas


Date Well completed 7-17- 19 80
Application for plugging filed 7-14 19 81
Application for plugging approved 7-15 19 81
Plugging commenced 8-7 19 81
Plugging completed 8-18 19 81

Reason for abandonment of well or producing formation
not productive

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leslie
Producing formation Depth to top Bottom Total Depth of Well 4756
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	395	None
				4 1/2	4749	2521

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Dumped in sand from 4658 to 4600'
4 sacks cement 4600 to 4550

Ripped pipe at 3200, 3100, 3000, 2800, 2700, 2525

Allied pumped in 15 gel, 8 hull, 10 gel
125 sacks 50-50 POZ, 4% gel, 3 - C.C.

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1981

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.
Elmo R. Morgenstern (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Elmo R. Morgenstern
Medicine Lodge, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of August, 19 81

Jessie Hamilton
Notary Public.

My commission expires April 4, 1982

Elmo on location when ripping.
Elmo not on location, Leslie on location
plugging well.

KANSAS DRILLERS LOG

COMPANY Texas Oil & Gas Corp.

SEC. 1 T. 28S R. 16W

FARM Binford NO. 1

LOC. 2310'FSL & 2310'FEL

COUNTY Kiowa

ROTARY TOTAL DEPTH 4,750'

COMM. July 7, 1980

COMP. July 17, 1980

CONTRACTOR H-30, INC. (Rig #5)

ISSUED August 1, 1980

CASING

10 3/4"

8 5/8" Set at 395' cemented w/400 sxs cement

ELEVATION 2,114' KTB

5 1/2"

4 1/2" Set at 4,749' cemented w/175 sxs cement

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed and Sand	450'
Red Bed and Shale	1,652'
Shale and Lime	2,095'
Lime and Shale	2,350'
Shale and Lime	2,717'
Lime and Shale	3,290'
Shale and Lime	3,451'
Lime and Shale	3,834'
Shale and Lime	4,140'
Lime and Shale	4,275'
Shale and Lime	4,410'
Lime and Shale	4,578'
Shale and Lime	4,640'
Lime and Shale	4,643'
Shale and Lime	4,671'
Lime and Shale	4,735'
Shale and Lime	4,850'
Rotary Total Depth	4,850'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

RECEIVED STATE CORPORATION COMMISSION


JUL 16 1981

CONSERVATION DIVISION Wichita, Kansas

Dean Britting (Signature)

State of Kansas)) ss: County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 1st day of August, 1980.



Elsie Willison - Notary Public (Signature)

My Commission Expires:

July 25, 1982