

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-21,043-6000

LEASE NAME John Heartso

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

4190 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 1 TWP. 28 SRGE. 16 ~~XXX~~ (W)

COUNTY Kiowa

Date Well Completed Oct., 1984

Plugging Commenced 11-23-92

Plugging Completed 12-03-92

LEASE OPERATOR McGinness Oil Company

ADDRESS 1026 Union Center Bldg., Wichita, KS

PHONE#(316) 267-6065 OPERATORS LICENSE NO. 5255

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 23, 1992 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Mississippi Depth to Top 4653' Bottom 4741' T.D. 4812'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	Surface	402	8-5/8"	400'	None
	Production	Surface	4812	5-1/2"	4792'	2350'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sand-off perforations to 4600'. Dumped 5-1/2 sacks cement with bailer.
Pumped 300 lbs of hulls, 5 sacks gel, 50 sacks of 60/40 PozMix, 5 sacks gel; pumped 100 lbs hulls, 150 sacks 60/40 PozMix.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hardtner Well Service License No. 39607-D

Address 150 North Main, Suite 1026, Wichita, Kansas 67202 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McGinness Oil Company 3-11-1993

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

I, Douglas H. McGinness II (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 1026 Union Center Bldg. Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 10th day of March, 19 93

[Signature]
Notary Public

Commission Expires: April 8, 1993

