


15-097-30171-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Kiowa County. Sec. 19 Twp. 28S Rge. 18W (E) (W)
Location as "NE/CNW/SW" or footage from lines C NE SW

Lease Owner Alpine Oil & Royalty Co., Inc.

Lease Name Cecil View Well No. 1

Office Address 800 Bitting Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed November 22 19 66

Application for plugging filed November 22, 1966 (by phone) 19

Application for plugging approved November 22, 1966 (by phone) 19

Plugging commenced November 22, 1966 19

Plugging completed November 22, 1966 19

Reason for abandonment of well or producing formation non-productive in commercial quantities

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5062 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	32 1/2 feet	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from total depth to 236 feet; plug and 1/4th sack hulls and 25 sacks cement at 236 feet. Heavy mud to 30 feet; plug, 1/2 sack hulls, mud and 1/2 sack cement at 30 feet; 10 sacks cement to bottom of cellar; 2 sacks cement for rat hole.

NOV 20 1966
CONSERVATION DIVISION
Wichita, Kansas

11-29-66

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

Address Sutton Place, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

800 Bitting Building, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 28th day of November 19 66

[Signature]
Evelyn Wanko
Notary Public.

My commission expires December 10, 1968

15-097-30171-0000

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

VIEUX #1
 C NE SW SECTION 19-28S-18W
 KIOWA COUNTY, KANSAS

COMMENCED: NOVEMBER 9, 1966
 COMPLETED: NOVEMBER 22, 1966

RECEIVED
 STATE GEOLOGICAL COMMISSION
 NOV 29 1966
 CONSERVATION DIVISION
 Wichita, Kansas

OPERATOR - ALPINE OIL & ROYALTY Co., Inc.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	65	CLAY	
65	165	SAND	
165	321	SHALE	RAN 9 JOINTS OF 8-5/8" CASING, SET @ 321' w/250 SACKS CEMENT.
321	470	SHALE	
470	525	RED BED	
525	1190	RED BED AND SHALE	
1190	1230	ANHYDRITE	
1230	1280	SHALE	
1280	1880	SHALE AND LIME	
1880	2220	SHALE AND SHELLS	
2220	2260	SHALE	
2260	2546	LIME	
2546	2885	LIME AND SHALE	
2885	2985	LIME	
2985	3150	LIME AND SHALE	
3150	3205	LIME	
3205	4060	LIME AND SHALE	
4060	4115	LIME	
4115	4240	SHALE	
4240	4305	LIME AND SHALE	
4305	4955	LIME	
4955	4979	LIME AND CHERT	
4979	5062	LIME	
5062	TD		DRY AND ABANDONED.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C NE SW SECTION 19-28S-18W, KIOWA COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 25TH DAY OF NOVEMBER, 1966, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

My COMMISSION EXPIRES FEBRUARY 1, 1968.