

15-097-20260-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Kiowa County, Sec. 10 Twp. 28 Rge. (E) 18 (W)
Location as "NE/CNWxSWx" or footage from lines. C NE NE
Lease Owner Abercrombie Drilling, Inc.
Lease Name EINSEL "B" Well No. #1
Office Address 801 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 11 1974
Application for plugging filed (verbal) October 11 1974
Application for plugging approved (verbal) October 11 1974
Plugging commenced October 11 1974
Plugging completed October 11 1974
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G.R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4851 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	440'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st Plug set @ 350' with 40 sacks cement
2nd Plug set @ 40' with 15 sacks cement
Plugged Rat Hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1974
CONSERVATION DIVISION
Wichita, Kansas

10-15-74

Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jack K. Wharton (employee of owner) or (owner or operator) of the above-described

well being filed, duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack K. Wharton
801 Union Center, Wichita, Kansas 67202
(Address)



Subscribed and sworn to before me this 14th day of October, 1974
Nancy E. Bledsoe
Nancy E. Bledsoe Notary Public.
My commission expires April 8, 1978

KANSAS DRILLERS LOG

IMPORTANT
 Kans. Geo. Survey request
 samples on this well.

S. 10 T. 28 R. 18 ⁸/_W
 Loc. C NE NE
 County Kiowa

API No. 15 — 097 — 20,260 - 6000
 County Number

Operator
Abercrombie Drilling, Inc.

Address
801 Union Center Wichita, Kansas 67202


Well No. #1 Lease Name Einsel "B"

Footage Location
660 feet from (N) line 660 feet from (E) line

Principal Contractor Abercrombie Drilling, Inc. Geologist Harold L. Steincamp

Spud Date September 30, 1974 Total Depth 4851' P.B.T.D.

Date Completed October 11, 1974 Oil Purchaser None



Locate well correctly
 Elev.: Gr. 2204'
 DF 2210' KB 2212'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"		440'	Common	325	3% Calcium Chloride 2% gel.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Pecker set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 15 1974
 CONSERVATION DIVISION
 Wichita, Kansas

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS Oil Disposition of gas (vented, used on lease or sold)	Gas bbls.	Water MCF	Gas-oil ratio bbls.	Producing interval (s)	CFPB

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Operator **Abercrombie Drilling, Inc.**

Well No. **#1**

Lease Name **EINSEL "B"**

Dry Hole

S 10 T 28S R 18 ^K/_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand	0	41	<u>ELECTRIC LOG TOPS</u>	
Sand & Shale	41	440	Heebner	4040
Shale	440	1915	Brown Lime	4202
Shale & Lime	1915	2655	Lansing	4214
Lime & Shale	2655	4254	Miss. Chert	4782
Lime	4254	4800	B/Miss. Chert	4816
Mississippian Chert	4800	4850	ELTD	4851
Rotary Total Depth		4850		
<p>DST #1 (4218-4230) 15", 30", 30", 30". Recovered 25' Mud. IFP 11#-18#; IBHP 513#; FFP 18#-18#; FBHP 143#.</p> <p>DST #2 (4238-4254) 15", 45", 60", 45". Strong blow. Gas to surface in 45". Recovered 62' Mud. IFP 35#-35#; IBHP 1320#; FFP 30#-35#; FBHP 1175#.</p> <p>DST #3 (4776-4800) 15", 30", 60", 45". Weak blow for 14", died. Good blow. Recovered 180 gas in pipe, 30' Mud. IFP 36#-36#; IBHP 466#; FFP 31#-31#, FBHP 964#.</p> <p>DST #4 (4805-4825) 15", 45", 45", 45". Weak blow for 15". Recovered 30' Mud with few oil spots. FFP's 31#; IBHP 36#; FBHP 36#.</p> <p>DST #5 (4762-4851) 30", 60", 60", 60" Fair blow. Recovered 45' Mud and 600' gas in pipe. IFP 35#-35#; IBHP 242#; FFP 40#-40#; FBHP 303#.</p> <p>D & A October 11, 1974</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Jack K. Wharton

Jack K. Wharton Signature

Geologist Title

October 14, 1974 Date

Date