

RECEIVED
 MAR 7 1983
 CONSERVATION DIVISION
 Wichita, Kansas

15-097-20925-0000

WELL PLUGGING RECORD

3-7-83

Give All Information Completely
 Make Required Affidavit

COUNTY Kiowa SEC. 7 TWP. 28 RGE. 18 W
 Location as in quarters or footage from lines:
1980' FNL & 1980' FWL of NW 1/4

	⊙		

Locate Well
 correctly on above
 Section Platt.

Lease Owner CINCO EXPLORATION COMPANY
 Lease Name Davis Estate Well No. 1
 Office Address P. O. Box 3723 - Victoria, Texas 77903
 Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole
 Date Well Completed 02/24/83
 Application for plugging filed 02/18/83
 Plugging commenced 02/23/83
 Plugging completed 02/24/83
 Reason for abandonment of well or producing formation
NON-COMMERCIAL

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Richard Lacey
 Producing formation NONE Depth to top bottom T.D. 4960'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put In	Pulled Out
	Fresh Water	0'	400'	8 5/8"	451	0
				4 1/2"	4959'	2486.9'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from
 feet to feet for each plug set.

Pumped mud into perforations at 4252'-56'. Left mud from 4256' to 4200'. Set
 CIBP at 4200'. Dumped 4 sacks of cement on top of CIBP. Cut casing at 2500'
 and pulled same.

Pumped 3 sacks of hulls, 15 gel and 70 sacks 50/50 Poz + 4% gel + 3% CaCl₂
 10 sacks gel, 1 sack hulls, wiper plug and 125 sacks cement as above.

This would leave cement as follows: (calculated)

- Cement - Surface to 500'
- Gel, hulls & Plug - 500' to 550'
- Cement - 550' to 850'

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services

STATE OF TEXAS COUNTY OF VICTORIA, ss.

MELVIN KLOTZMAN (employee of owner) or ~~XXXXXXXXXXXXXXXXXXXX~~ of
 the above-described well, being first duly sworn on oath, says: That I have knowledge
 of the facts, statements, and matters herein contained and the log of the above-described
 well as filed and that the same are true and correct. So help me God.

(Signature)

P.O. Box 3723-VICTORIA, TX 77903
 (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 1983

Bonnie Jean Mann

My Commission Expires: 2/06/85