

WELL PLUGGING RECORD

15-097-20975-0000

Give All Information Completely
 Make Required Affidavit

COUNTY Kiowa SEC. 7 TWP. 28 RGE. 18 E/W
 Location as in quarters or footage from lines:
1980' FNL & 1980' FWL of NW $\frac{1}{4}$

Locate Well
 correctly on above
 Section Platt.

Lease Owner Cinco Exploration Company
 Lease Name Davis Estate Well No. 1
 Office Address Box 3723 Victoria, Texas 77903
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry hole
 Date Well Completed Feb. 24, 1983
 Application for plugging filed Feb. 18, 1983
 Plugging commenced Feb. 23, 1983
 Plugging completed Feb. 24, 1983
 Reason for abandonment of well or producing formation not economical to produce

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Richard Lacey
 Producing formation None Depth to top bottom T.D. 4960'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Fresh water	0	400	8 5/8"	451	0
				4 1/2"	4959'	2486.9

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from feet
 to feet for each plug set.


Pumped mud into perforations at 4252'-56'. Left mud from 4256 to 4200'. Set
CIBP at 4200'. Dumped 4 sacks of cement on top of CIBP. Cut casing at 2500' and
pulled same.

Pumped 3 sacks of hulls, 15 gel and 70 sacks 50/50 Poz plus 4% gel plus 3% Cal. Chloride.
10 sacks gel, 1 sack hulls, wiper plug and 125 sacks cement at above. This would
leave cement as follows: Cement --surface to 500'.
Gel, hulls and plug 500 to 550'.
Cement 550-850'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pratt Well Service, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.
Judy Baird (employee of owner) or (~~owner~~) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.



(Signature) Judy Baird
Box 847 Pratt, Ks. 67124
 (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of March, 19 83

Charlene M. Dudrey
 Notary Public.

My Commission expires: 9/10/86

RECEIVED
 STATE CORPORATION COMMISSION

MAR 20 1983

3-28-83