

API NUMBER 15-097-21,053-000

LEASE NAME Wheeler

WELL NUMBER 1-26

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

660 Ft. from S/W Line of Section (circle one)

1980 Ft. from E/W Line of Section (circle one)

LEASE OPERATOR Paleozoic Prospects, Inc.

SPOT LOCATION C - NE - NW

ADDRESS P.O. Box 780002

SEC. 26 TWP. 28 S. RGE 17 (E) or (W)

CITY, STATE, ZIP Wichita, Ks. 67278-0002

COUNTY Kiowa

PHONE# (316) 776-0367 OPERATORS LICENSE NO. 31872

Date Well Completed _____

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced July 9, 1997

Date Plugging Completed Aug 19, 1997

The plugging proposal was approved on June 2, 1997 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation(s) Stone Corral Formation Depth to Top _____ Bottom _____ T.D. 4950'

Show depth and thickness of all water, oil and gas formations. Perfs and Plugs 4240'-43'

OIL, GAS OR WATER RECORDS Elev. 2172' G.L. CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
	Surface	0	480'	8 5/8"	480'	0
	Casing	0	4950'	4 1/2"	4950'	2450'

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Set bridge plug at 4190' w/ 2 sx cement on top. Cut off at 2450'.
Pumped 300# Hulls, 10 sx Gel. 50 sx 60/40/6 at 450#, 10 sx Gel at
600#, 100# Hulls at 750#, Release Plug, 150 sx 60/40/6 at 600#, 60'
from surface to top of cement, fill back w/ sand & top off w/ 1 sx cement.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service

License No. 5893

Address Box 847, Pratt, Kansas 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Paleozoic Prospects, Inc

STATE OF Kansas COUNTY OF Pratt, ss.

Stephen E. Hart (Employee of Operator or (Operator) of above-described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephen E. Hart

(Address) c/o P.W.S. Inc.

SUBSCRIBED AND SWORN TO before me this 20th day of August, 1997

Kenneth W. Furgason
Notary Public

My Commission Expires: June 19, 2000



8-21-97

RECEIVED
KANSAS CORP. COM.
FORM CP-4
REVISED 12-5