


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County. Sec. 20 Twp. 28S Rge. 17W R/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
SE SW NW
Lease Owner Voyager Petroleum, Inc. c/o Godsey-Earlougher
Lease Name M. Hart #1 Well No. 1
Office Address 7030 South Yale, Tulsa, Oklahoma 74136
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed January 5, 1977 19
Application for plugging filed January 5, 1977 19
Application for plugging approved January 5, 1977 19
Plugging commenced 9:00 AM, January 5, 1977 19
Plugging completed 11:00 AM, January 5, 1977 19
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Depth to top Bottom Total Depth of Well 4885'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS
RECEIVED
STATE CORPORATION COMMISSION

CASIN; RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
MAR 01 1977				8 5/8"	462'	None

3-01-77
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Filled hole with heavy mud.
Heavy mud to 460', 35 sacks cement;
heavy mud to 40', Halliburton plug,
1/4 sack hulls, 15 sacks cement; 5 sacks
in rathole; 5 sacks in mousehole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STERLING DRILLING COMPANY
P. O. Box 129, Sterling, Kansas 67579


STATE OF KANSAS COUNTY OF RICE
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January 19 77

CHARLES HALL—NOTARY PUBLIC
My Commission Expires Jan. 6, 1978

Charles M. Hall, Notary Public.



15-097-2036-0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- M. HART #1
Located: SE SW NW, Section 20-28S-17W, Kiowa County,
Kansas

OWNER: Voyager Petroleum, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 17, 1976
COMPLETED: January 5, 1977

TOTAL DEPTH: 4885'

<u>LOG</u>		<u>CASING RECORD</u>
0 - 250-	Shale, Bed Bed	Ran 11 joints 8 5/8" casing, 451' set at 462' K.B. Cemented with 375 sacks Pozmix #1 with 3% cc. Plug down at 9:00 PM, 12-17-76.
250 - 950	Shale	
950 - 4320	Lime and Shale	
4320 - 4325	Lime	
4325 - 4465	Lime and Shale	
4465 - 4540	Lime	
4540 - 4660	Lime and Shale	
4660 - 4790	Lime and Chert	
4790 - 4840	Lime, Chert, Shale	
4840 - 4885	Chert	Plugged.

RECEIVED
STATE CORPORATION COMMISSION

MAR 01 1977

CONSERVATION DIVISION
Wichita, Kansas