

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bachus Oil Co.

Complete Address 721 E Central Wichita, Ks

Lease Name B Sterling C Well No. 2

Location SW/SE/NE Sec. 36 Twp. 34 Rge. 13 (E) (W) W

County Barber Total Depth 4880

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering Inc.

Address Box 698 Great Bend, Ks License No. 670

Operation Completed: Hour 11:00 AM Day 23 Month 10 Year 1971

The above well was plugged as follows:

321 ft 8 5/8 surface pipe cemented with 150 sacks. 4879 ft 4 1/2 long
string cemented with 200 sacks. Top perf. 4818 ft. Sand back to
4800 ft, 4 sacks cement with bailer. Pulled 4000 ft 4 1/2. Set 20 ft
rock bridge at 260 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed [Signature]
Well Plugging Supervisor

INVOICED

DATE 10/28/71
INV. NO. 4536-4