

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- 129-20,576-0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name ANADARKO PRODUCTION COMPANY

Complete Address BOX 351 LIBERAL, KANS. 67901

Lease Name PARSLON Well No. "A"-#1

Location SW - NW Sec. 2 Twp. 34 Rge. 42 (East) (West)

County MORTON Total Depth 5300 FE

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor JOHNSON RIG. (3)

Address 681 LILAC, LIBERAL, KANS. License No. _____

Operation Completed: Hour: 10:30 PM Day: 15th Month: OCT Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

1/200 ST COMMON - 2% CA-CC.
8 5/8" - 1309 FE SP. CMT. 1/500 ST 50/50 FORMIX 4% GEL - 2% C.C.
ORDERED 120 ST COMMON CMT. & 2 - 8 5/8" PLUGS.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1ST PLUG - @ 2850 FE 1/40 ST CMT.

2ND PLUG - @ 1290 FE + WIPER PLUG. 1/60 ST CMT.

3RD PLUG. @ 480 FE 1/30 ST CMT.

4TH PLUG -> SOLID BRIDGE @ 40 FE TO 1/10 ST CMT.

5TH CMT IN RAT HOLE

5TH CMT. IN MOUSE HOLE CEMENTED BY DOWEL.

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION
Signed: Marion Schmidt
Conservation Division Agent

DATE 11-19-81

INV. NO. 8301-W

OCT 19
10-19-81
CONSERVATION DIVISION
Wichita, Kansas