

KANSAS

RECEIVED
Form CP-3
STATE CORPORATION COMMISSION
Rev. 6-4-68

STATE CORPORATION COMMISSION

SEP 14 1976

CONSERVATION DIVISION AGENT'S REPORT

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

Authority issued Aug 25, 1976
API Number 15 - 129 - 10552-0000 (of this well)

Operator's Full Name Pan Eastern Exploration Co.

Complete Address P.O. Box 828, Liberal Kans-67901

Lease Name Riley "B" Well No. 1-15

Location app C/ NW. NW. SE. Sec. 15 Twp. 34 Rge. (E) (W) 47

County Morton Total Depth 3231

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargents Casing Pulling Service

Address Liberal Kans 67901 License No. 511

Operation Completed: Hour 4:00 PM Day 10 Month Sept Year 1976

The above well was plugged as follows:

There was 600' of 10 3/4" Surface casing
7" casing set to 3200'. Plug back to
3108'. Perforations from 3071' to 2893'.
1st plug 50 sacks + 3 pills at 3071.
2nd plug at 1000' with 25 sacks cement.
3rd plug at 600' with 25 sacks cement.
4th plug at 40-0 with 20 sacks cement.
There was 1061' of 7" salvage

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Lawrence Thomas
Well Plugging Supervisor

DATE 9/14/76

INV. NO. 3813-W