

KANSAS

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued June 23, 1967.

JUL 5 1967
7-5-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

Lease Name LaVelle Well No. # A-1

Location C SW NW Sec. 1 Twp. 28 Rge. 14 (E) (W)W

County Pratt Total Depth 4603'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling, Inc.

Address Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 4:00 P.M. Day 28th Month June Year 1967

The above well was plugged as follows:

346' of 8 5/8" surface pipe, cement circulated. 4599' of 4 1/2" long string, with
the temperature survey at 3888'. Plug back T.D. 4170'. Top perforation 4047'.
Bottom of the hole was sanded to 4000', and cemented with 4 sacks, through the
dump bailer. 3300' of 4 1/2" long string was recovered from the hole. Bridge plug
was pushed in fluid to 350', bridge plug and rock bridge from 350' to 340'. 5
sacks of cement was mixed in a barre, and put on plug at 340', through the
dump bailer, and let set over-night. Next day hole was bailed dry, and 20 sacks
of cement was added to the plug. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Ebling
Well Plugging Supervisor

DATE 7/5/67
INV. NO. 5521-W