

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20534-00-00
Spot: N2S2SW Sec/Twnshp/Rge: 4-17S-27W
999 feet from S Section Line, 3915 feet from E Section Line
Lease Name: KUEHN Well #: 3
County: LANE Total Vertical Depth: 4531 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1200		WITH 2 SX CMT
CIBP		2050		WITH 20 SX CMT
PROD 4.5		4264	0	WITH 225 SX CMT
SURF 8.625		324		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/10/2015 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JASON SCHULER Company: ABERCROMBIE ENERGY LLC Phone: (620) 793-8186

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/10/2015 3:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

A RETRIEVABLE BRIDGE PLUG AT 4060' COULD NOT BE RETRIEVED SO 20 SX CMT WAS PUMPED ON TOP OF THE BRIDGE PLUG. SET CIBP @ 2050' WITH 20 SX CMT. SET CIBP @ 1200'. PRESSURED TO 750# & HELD FOR 5 MINUTES. DUMPED 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. RAN CBL. SPOTTY CEMENT AT 1200' & GOOD CEMENT AT 900'. PERFORATED AT 1175' & ESTABLISHED A PUMP RATE OF 2 BPM @ 600#. PUMPED 45 SX CMT, 50# HULLS, 45 SX CMT THROUGH PERFS WITH 10 BBL WATER FOR DISPLACEMENT. PERFORATED AT 350' & CIRCULATED CMT TO SURFACE WITH 113 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4177	4181		
4152	4156		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

6/24/15 CKM

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
JUN 16 2015
KCC DODGE CITY

SA

KCC WICHITA

JUN 19 2015 Form CP-2/3

RECEIVED