

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-00129-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 7-34S-26W
1250 feet from S Section Line, 2540 feet from E Section Line
Lease Name: CLASSEN Well #: 1-7
County: MEADE Total Vertical Depth: 6143 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	6148	2858	WITH 100 SX CMT
SURF	8.625	1377		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/15/2015 10:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: KAMERON WILSON Company: BEREXCO LLC Phone: (316) 772-2971

Proposed Plugging Method: CIBP @ 5880' WITH 2 SX CMT. PLUG AT 1430' WITH 10 SX GEL & 50 SX CMT. PLUG AT 150' CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: ROBERT DICKERSON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/15/2015 1:20 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

PUMP 30 SX CMT & 100# HULLS AT 5818'. 1ST PLUG AT 1441' WITH 10 SX GEL & 50 SX CMT. CIRCULATED. 2ND PLUG AT 147' WITH 95 SX CMT. CIRCULATED. CMT FELL BACK. TOPPED OFF WITH 15 SX CMT & IT FELL BACK. 6/2/15: TOPPED OFF WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5934	6036		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

6/24/15 CKM

District: 01

Signed *[Signature]*
(TECHNICIAN)

RECEIVED
JUN - 8 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUN 15 2015
CONSERVATION DIVISION
WICHITA, KS