

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-153-21103-00-00
Spot: S2NESENE Sec/Twnshp/Rge: 19-1S-32W
1840 feet from N Section Line, 330 feet from E Section Line
Lease Name: SIMMINGER Well #: 1
County: RAWLINS Total Vertical Depth: 4175 feet

Operator License No.: 33263
Op Name: BOWMAN, WILLIAM F. DBA THE BILL
Address: 2640 WRD
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4172		180 SX
SURF	8.625	288		200 SX

Well Type: OIL UIC Docket No.: _____ Date/Time to Plug: 06/10/2015 10:30 AM
Plug Co. License No.: 34821 Plug Co. Name: K & M WELL SERVICE INC.
Proposal Rcvd. from: BILL BOWMAN Company: BOWMAN OIL COMPANY INC. Phone: (785) 259-1297

Proposed Plugging Method: 8 5/8" surface casing set at 288' w/200 sx cement.
5 1/2" production casing set at 4172' w/180 sx cement.
TD 4175'. Perforations: 3936', 3970' - 3975', 4012' - 4015' and 4118' - 4121'.
Dakota exempt area. 300 sx GMD cement pumped down from top between 5 1/2" casing and well-bore.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/10/2015 1:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 2745' and 2115'. Ran tubing to 4100' and pumped 8 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 2800' and pumped 140 sx cement w/200 # hulls. Pulled tubing to 1400' and pumped 165 sx cement w/100 # hulls. Circulated with cement. Pulled tubing to surface and topped off casing with 20 sx cement. Connected to 8 5/8" surface casing with immediate pressure of 300 psi.

GPS: 39.95378N -100.94569W

Perfs:

Top	Bot	Thru	Comments
4118	4121		
4012	4015		
3970	3975		
3936	3936		

Remarks: CONSOLIDATED OILWELL SERVICES TICKET # 47,973

Plugged through: TBG

6/24/15 ckm

District: 04

Signed Darrel Dipman
(TECHNICIAN) CM

JUN 15 2015

KCC WICHITA

JUN 22 2015

RECEIVED