

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-23974-00-00  
Spot: SENWSWSW Sec/Twnshp/Rge: 22-10S-20W  
900 feet from S Section Line, 405 feet from W Section Line  
Lease Name: ROGERS Well #: 4  
County: ROOKS Total Vertical Depth: 3771 feet

Operator License No.: 6931  
Op Name: BOWMAN OIL COMPANY, A GENERAL  
Address: 805 CODELL RD  
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3769		150 SX
SURF	8.625	230		150 SX
T1	2.875	3766		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/05/2015 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DONALD A. BOWMAN Company: BOWMAN OIL CO. Phone: (785) 259-4154

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
DV Tool at 2250', cwc w/480 sx cement.  
Production perforations: 3209' - 3740'

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/05/2015 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3674' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2765' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1739' and pumped 110 sx cement to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing w/15 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 10 sx cement. Shut in pressure 200 psi.

GPS: 39.16416N -099.54794

Perfs:

Top	Bot	Thru	Comments
3739	3740		
3705	3706		
3520			
3480	3484		
3462	3466		
3432	3436		
3334	3338		
3209	3213		

Remarks: ALLIED TICKET # 55779

Plugged through: TBG

6/24/15 CPM

District: 04

Signed Pat Bedore  
(TECHNICIAN)

CM

KCC WICHITA

JUN 18 2015

RECEIVED

JUN 09 2015