

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-20077-00-02  
Spot: SWSWNE Sec/Twnshp/Rge: 18-7S-19W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: BERLAND TRUST Well #: 1  
County: ROOKS Total Vertical Depth: 3513 feet

Operator License No.: 31171  
Op Name: CONTINENTAL OPERATING CO.  
Address: 1221 MCKINNEY STREET, STE 3700  
HOUSTON, TX 77010

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 4.5   | 3498       |             | 300 SX   |
| SURF   | 8.625 | 206        |             | 125 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/03/2015 10:00 AM  
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE  
Proposal Rcvd. from: RALPH BRUNGARDT Company: CONTINENTAL OPERATING Phone: (785) 735-4645

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Open Hole- 3498' - 3513'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/03/2015 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 3300' and pumped 80 sx cement w/100 # hulls. Pulled tubing to 2300' and pumped 80 sx cement w/100 # hulls. Pulled tubing to 1200' and pumped 100 sx cement to circulate cement to surface. Pulled all tubing and topped off 4 1/2" casing w/15 sx cement. Visually checked 8 5/8" x 4 1/2" annulus and cement was to surface.

GPS: 39.44568N -099.48091W

Remarks: GLOBAL TICKET # 1669

Plugged through: TBG

6/24/15 CKM

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

KCC WICHITA

JUN 18 2015

RECEIVED

JUN 09 2015