

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22768-00-00
Spot: S2SWNWSW Sec/Twnshp/Rge: 27-13S-21W
1435 feet from S Section Line, 330 feet from W Section Line
Lease Name: BERTHA RIEDEL Well #: 2-27
County: TREGO Total Vertical Depth: 4235 feet

Operator License No.: 35144
Op Name: CYNOSURE ENERGY, LLC
Address: 3 CHURCHILL DR.
CHERRY HILLS VILLAGE, CO 80113

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4220		470 SX
SURF	8.625	254		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/11/2015 9:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Revd. from: TERRY PIESKER Company: QUALITY OIL WELL CEMENTING Phone: (785) 735-4363

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 17 sx gel and 400 # hulls.
CIBP 4080'
Perforations: 4010' - 4047' and 4100' - 4104'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/11/2015 1:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4003' and pumped 17 sx gel followed by 50 sx cement w/150 # hulls. Pulled tubing to 1823' and pumped 100 sx cement w/50 # hulls. Pulled tubing to 928' and pumped 115 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 25 sx cement. Tied on to backside and squeezed with 0 sx. 100 psi.

GPS: 38.88914 -099.65031

Perfs:

Top	Bot	Thru	Comments
4100	4104		
4010	4047		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1162

Plugged through: TBG

District: 04

Signed _____

(Signature)
(TECHNICIAN) 6/24/15 CKM
CM

KCC WICHITA
JUN 22 2015
RECEIVED

JUN 12 2015