

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-21493-00-00
Spot: SESWNW Sec/Twnshp/Rge: 9-25S-18W
2679 feet from N Section Line, 660 feet from W Section Line
Lease Name: MCLEAN Well #: 1
County: EDWARDS Total Vertical Depth: 4707 feet

Operator License No.: 34402
Op Name: GARAL, DONNA AND VINCENT INNON
Address: 30-38 48 ST
ASTORIA, NY 11103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4450		
PROD	5.5	4710	2410	WITH 150 SX CMT
SURF	8.625	349		WITH 225 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/11/2015 12:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK TO 4050' WITH 5 SX CMT. PLUG AT 1265' WITH 10 SX GEL & 50 SX CMT. PLUG AT 380' WITH 50 SX CMT. PLUG AT 40' TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/11/2015 2:15 PM

KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SANDED BACK TO 4020' WITH 5 SX CMT. 1ST PLUG AT 1255' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 34' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4607	4612		
4552	4558		
4122	4123		** not on ACO1, but

KCC WICHITA
JUN 19 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

6/24/15 CKM

District: 01

Signed Robert Dickerson

(TECHNICIAN)

RECEIVED
JUN 17 2015
KCC DODGE CITY