

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25536-00-00
Spot: NWSWSENE Sec/Twnshp/Rge: 3-17S-15W
2229 feet from N Section Line, 1164 feet from E Section Line
Lease Name: D.STEINERT Well #: 1
County: BARTON Total Vertical Depth: 3620 feet

Operator License No.: 34674
Op Name: H & D EXPLORATION LLC
Address: 165 WEST 1ST PO BOX 387
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3505		170 SX
SURF	8.62	492		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/11/2015 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Revd. from: GERLARD ACHATZ Company: H & D EXPLORATION Phone: (620) 653-4791

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 14 sx gel and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/11/2015 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 475', 1000' and 1500'. Ran tubing to 3450' and pumped 14 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1500' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 500' and pumped 55 sx cement w/100 # hulls. Cement circulated out the backside. POOH. Hooked to casing and pumped 100 sx cement. Cement circulated out the braden head. Shut in.
GPS: 38.60294 -098.96400

Perfs:

Top	Bot	Thru	Comments
3446	3456		
3424	3432		
3408	3414		

Remarks: QUALITY CEMENTING TICKET # 1096

Plugged through: TBG

6/24/15 CKM

District: 04

Signed Ray A. Dinkel
(TECHNICIAN) CKM

KCC WICHITA

JUN 22 2015

RECEIVED

JUN 17 2015